



# LINUO SOLAR

# 685W-710W

## Topcon

Monocrystalline PV Module  
LSTDMGH132P Series



SMBB technology, higher component power



Double-sided power generation



Dual stage 100% EL Inspection



Lower power attenuation higher generation returns



N-type double glass, excellent PID resistance




Ammonia & salt mist resistant

### Comprehensive Certificates

- IEC61215, IEC61730
- TUV, CE
- ISO9001: 2015
- ISO14001: 2015
- ISO45001: 2018





### Superior Warranty





## Mechanical Specifications @STC

Solar Cells:	Mono
Number of Cells:	132pcs
Module: :	2384×1303×30mm
Weight:	38.7 kg±3%
Snow/Wind Load:	5400/2400 Pa
Thickness of Glass:	dual 2.0mm
Junction Box:	IP68, 3 Diodes
Connector:	HTC-16, IP68
Length:	(+)250mm /(-)300mm(including connector)




## Electrical Specifications @STC

P <sub>max</sub> (W) 0-+5W	U <sub>mpp</sub> (V)	I <sub>mpp</sub> (A)	U <sub>oc</sub> (V) ±3%	I <sub>sc</sub> (A) ±3%	Module Efficiency	Max System Voltage	Max Series Fuse	Bifacial Gain 5% (W)	Bifacial Gain 15% (W)	Bifacial Gain 25% (W)
685	40.0	17.13	47.7	18.15	22.05%	1500V	35A	712	767	822
690	40.2	17.16	47.9	18.18	22.21%	1500V	35A	718	773	828
695	40.4	17.20	48.1	18.22	22.37%	1500V	35A	723	778	834
700	40.6	17.24	48.3	18.26	22.53%	1500V	35A	728	784	840
705	40.8	17.28	48.5	18.31	22.70%	1500V	35A	733	790	846
710	41.0	17.32	48.7	18.35	22.86%	1500V	35A	738	795	852

## Temperature Parameter

Temperature Cycling Range:	-40°C ~ +85°C
Norminal Module Operating Temperature:	45±2 °C
Temperature Coefficient of I <sub>sc</sub> :	0.042%/°C
Temperature Coefficient of V <sub>oc</sub> :	-0.257%/°C
Temperature Coefficient of P <sub>max</sub> :	-0.300%/°C
Bifacial Ratio:	80%±5%

## I-V Curve LSTDMGH132P-700W



## Packaging Configuration

Modules Per Pallet:	36pcs
Modules Per 40 ' HQ:	648pcs

## Guarantee

12-year warranty on materials & workmanship  
30-year linear power output warranty

\* Specifications subject to technical changes and tests, Linuo Power reserves the right of final interpretation.